DETAILED OPERATING PLAN FOR COLUMBIA RIVER TREATY STORAGE

1 AUGUST 1988
THROUGH 31 JULY 1989

COLUMBIA RIVER TREATY OPERATING COMMITTEE

NOVEMBER 1988

DETAILED OPERATING PLAN
FOR COLUMBIA RIVER TREATY STORAGE
1 AUGUST 1988 THROUGH 31 JULY 1989

1. REFERENCES AND INTERPRETATION

In this document:

A. "Principles and Procedures" means the document "Principles and Procedures for the Preparation and Use of Hydroelectric Operating Plans," dated May 1983;

B. "Assured Operating Plan" means the document "Columbia River Treaty Hydroelectric Operating Plan-Assured Operating Plan for Operating Year 1988-1989," dated October 1983;

C. "Flood Control Plan" means the document "Columbia River Treaty Flood Control Operating Plan," October 1972;

D. "Operating Year" means the period from 1 August 1988 through 31 July 1989;

E. "Operating Committee" means the Columbia River Treaty Operating Committee;

F. "Detailed Operating Plan" means a detailed operating plan prepared for the Operating Year by the Operating Committee pursuant to the Principles and Procedures and consisting of the contents of this document;

G. "Runoff Volume Forecast Program for Canadian Columbia River Treaty Reservoirs" means the document of that title dated 15 August 1969, with subsequent modifications as agreed by the Operating Committee.

H. "Actual Energy Regulation" means the simulated hydroregulation study performed by the Coordinating Group that reflects actual streamflow conditions.

2. PREPARATION AND SCOPE

This Detailed Operating Plan has been developed from the Coordinated System's final regulation for the 1988-89 Operating Year. System load and resource estimates, duration of critical period, flood control and other criteria have been reviewed and revised in accordance with the Principles and Procedures as necessary. The Critical Period duration is 42 months extending from 1 September 1988 through 31 February 1992 with hydro capability based on the 1928-29 through 1931-32 water years.

The data, criteria, and procedures presented herein will be used as described for the formation and use of Operating Rule Curves for each of the Canadian storage reservoirs, Duncan, Arrow, and Kinbasket Lake (Mica), and for the whole of Canadian storage as well as Lake Koocanusa (Libby).

The Entity agreement on the downstream benefit computation for the 1988-89 Operating Year indicated that the U.S. Entity is entitled to receive from B.C. Hydro and Power Authority 2.8 average megawatts during the period 1 August 1988 through 31 March 1989 and 3.4 average megawatts during the period 1 April through 31 July 1989. Suitable arrangements for delivery of this energy have been made between the Bonneville Power Administration and B.C. Hydro.

The usable Columbia River Treaty storage space available for power purposes during the Operating Year is 15.5 million acre-feet in Canada and 4.9795 million acre-feet at Libby in the United States, distributed as follows:

Duncan Reservoir

1.4 million acre-feet (705.8 thousand second-foot-days) between elevations 1892.0 feet and 1794.2 feet measured at Duncan forebay. (Based on B.C. Hydro table dated 21 February 1973.)

Arrow Reservoir

7.1 million acre-feet (3579.6 thousand second-foot-days) between elevations 1444.0 feet and 1377.9 feet measured at Fauquier, B.C. (Based on B.C. Hydro table dated 28 February 1974.)

Kinbasket Lake (Mica)

7.0 million acre-feet (3529.2 thousand second-foot-days) measured at Mica forebay. (Based on B.C. Hydro table dated 25 March 1974.)

Lake Koocanusa (Libby)

4.9795 million acre-feet (2510.5 thousand second-foot-days) between elevation 2459.0 feet and 2287.0 feet measured at Libby forebay.

The usable Canadian storage available for normal flood-control purposes for the Operating Year is 1.27 million acre-feet in Duncan Reservoir below elevation 1892.0 feet; 5.1 million acre-feet in Arrow Reservoir below elevation 1444.0 feet; and 2.08 million acre- feet in Kinbasket Lake (Mica Reservoir) except that additional storage may also be operated for flood control purposes under special circumstances, as described in the Flood Control Operating Plan. The foregoing assumes a 2.0 million acre-feet transfer of flood-control storage from Arrow Reservoir to Kinbasket Lake as detailed in the Flood Control Operating Plan.

3. OPERATING RULE CURVE

The Operating Rule Curve for the whole of Canadian Storage shall be the sum of the Operating Rule Curves for each of Duncan, Arrow, and Mica. The Operating Rule Curve for each of the Duncan, Arrow, and Mica Reservoirs during the period 1 August 1988 through 31 July 1989 is determined in accordance with the reference documents of Section 1, and is defined as follows:

A. During the period 1 August 1988 through 31 December 1988, it is the higher of the First Critical Rule Curve or the Assured Refill Curve.

B. During the period 1 January 1989 through 31 July 1989 it is the higher of the First Critical Rule Curve or the Assured Refill Curve, unless the Variable Refill Curve is below the higher of the above two curves; then it is defined by the Variable Refill Curve.

C. During the period 1 January 1989 through 31 March 1989 it will not be lower than a limiting rule curve designed to protect firm loads with recurrence of 1936-37 hydro conditions unless a lower reservoir elevation is required for flood control (Exhibit 5).

D. During any period in the 1988-89 Operating Year, it will not be higher than the Upper Rule Curve, defined as the maximum elevation of each reservoir established by flood control requirements and may be modified on mutual agreement for construction and other contingency requirements.

E. Operation of Mica will be in accordance with the monthly average outflows tabulated with specified qualifications under Operating Limits. The obligation to operate Mica to produce optimum benefits in Canada and downstream in the United States will be deemed to have been fulfilled by operating to these criteria.

F. The Variable Refill Curves for Duncan and Mica shall be constructed based on the power discharge requirement specified in Exhibit 6.

G. The Variable Refill Curve for Arrow shall be constructed as specified below:

(1) If the projected live Mica storage content at the end of the current month using most likely Mica inflow and target outflows (expected live Mica storage content) is less than that computed for the Variable Refill Curve for Mica, the Variable Refill Curve for Arrow will be calculated using:

(a) The forecast volume of inflow for Arrow excluding the volume of inflow above the Mica project (Arrow local inflow). This volume will be reduced by a forecast error such that there is a 95 percent probability that the reduced forecast is equalled or exceeded.

(b) The total Mica target outflow as specified in 6C will be added to the forecast volume described in (a) above.

(c) In computing water available for refill of Arrow Reservoir the power discharge requirements for Arrow as specified in Exhibit 6 will be deducted from the volume calculated in (B).

(d) For the purpose of calculating the rule curve for the whole of Canadian storage, the Variable Refill Curve for Mica will be set equal to the expected live Mica storage content.

(2) If the expected live Mica storage content is greater than that computed for the Variable Refill Curve for Mica, the Variable Refill Curve for Arrow will be computed using the total Arrow inflow method, i.e., the forecast volume of inflow above the Mica project will be included. The space in Mica to be deducted from the Arrow total inflow will be equal to the amount of storage draft determined by the Operating Rule Curve for Mica as defined in paragraphs 3B and 3C.

The Operating Rule Curve for Libby Reservoir is defined in a manner similar to that for Canadian storage.

4. OPERATIONS

The operation of Treaty storage by the Columbia River Treaty Operating Committee during the period 1 August 1988 through 31 July 1989 will be in accordance with the reference documents of Section 1, and the following operating guides:

A.	First Critical Rule Curve and Assured Refill Curve for Duncan, Arrow, and Mica and the whole of Canadian storage.	Exhibit 1
B.	Second Critical Rule Curve for Duncan, Arrow, and Mica and the whole of Canadian storage.	Exhibit 2
C.	Third Critical Rule Curve for Duncan, Arrow, and Mica and the whole of Canadian storage.	Exhibit 3
D.	Fourth Critical Rule Curve for Duncan, Arrow, and Mica and the whole of Canadian storage.	Exhibit 4
E.	Limiting Rule Curve based on 1936-37 Hydro Conditions.	Exhibit 5
F.	Variable Refill Curve Procedures.	Exhibit 6
G.	The First, Second, Third, and Fourth Critical Rule Curves and Energy Content Curve for Libby.	Exhibit 7

H. Duncan Reservoir Capacity Table. Exhibit 8
(Based on B.C. Hydro table dated 21 February 1973)

I. Arrow Lakes, Reservoir Capacity Table. Exhibit 9
(Based on B.C. Hydro Combined Storage Table dated 28 February 1974.)

J. Mica Reservoir Capacity Table. Exhibit 10
(Based on B.C. Hydro table dated 25 March 1974.)

K. Libby Storage Above Elevation 2287 feet. Exhibit 11

5. SCHEDULING STORAGE REGULATION

A. The Operating Committee will exchange all current operating data necessary for the regulation of Canadian storage projects as soon as available, including the beginning and end of the flood control season.

B. Seasonal runoff volume forecasts for Canadian Treaty Projects shall be made available by the Canadian Section no later than the seventh of each month, as required. Forecasts of seasonal runoff volume at periods other than those representing month-end conditions may be requested by the Operating Committee if hydrologic conditions warrant. Seasonal runoff volume forecasts for the Columbia River at The Dalles, Oregon, shall be made available by the U.S. Section on the second working day of each month as required.

C. Unless otherwise agreed, requests by the U.S. Section of the Operating Committee for the regulation of the Canadian storage content will be made to the Canadian Section on a regular basis in accordance with the following procedures:

(1) Weekly Requests for Storage Regulation During the Storage Drawdown Season

(a) Timing of Requests. A preliminary request will be made not later than noon each Thursday, followed by a final request by noon Friday, if necessary.

(b) Confirmation of Requests. Written confirmation of the request will be dispatched on Friday in accordance with the following format unless otherwise agreed: This message will confirm our verbal request of this date for the (storing/drafting) of _____ ksfd (in/from) the whole of Canadian storage for the period _____ through _____. This request is based on an estimated average regulated inflow of _____ kcfs to Arrow Reservoir, _____ kcfs to Duncan Reservoir, _____ kcfs to Mica Reservoir, and _____ kcfs to Libby Reservoir during the above mentioned period, and an average discharge of _____ kcfs from the Arrow Project, _____ kcfs from the Duncan Project, _____ kcfs from the Mica Project, and _____ kcfs from the Libby Project.

(c) Period Covered by Request. The period covered by the request shall be from 0800 hours on the Saturday following the date of weekly request to 0800 hours on the Saturday a week later. Changes from the previous week's request shall commence at 0800 hours on Saturday, or as soon thereafter as permitted by the limits of 6B(6).

(d) Release Determination. The amount of water released or stored during the period of the request will be determined by the changes in reservoir contents based on the recorded lake stage and storage capacity tables for Duncan (Exhibit 8), Arrow (Exhibit 9), and Mica (Exhibit 10). The change in Arrow storage content will be determined using the recorded lake stage at the gauge near Fauquier, B.C.

(e) Delivery. Requested storage releases will be made effective at the Canadian-United States border. The request will be deemed to have been fulfilled if the total amount of storage water requested is released from Duncan, Arrow, and Mica reservoirs, provided an amount equal to or greater than the storage water release from Duncan reservoir is concurrently discharged from Kootenay Lake.

(f) Modification. If any modification to a written request is agreed by the Operating Committee, a further written request superseding the original written request will be dispatched immediately by the U.S. Section of the Operating Committee to the Canadian Section of the Operating Committee.

(g) Nonroutine Operation. Any special operation which is agreed by the Operating Committee will be suitably documented.

(2) Daily Request for Storage Regulation During the Flood Control Season

(a) Forecasts. Day-to-day streamflow forecasts will be accomplished by use of computer simulation by the Columbia River Forecasting Service. The regulation center required by the Flood Control Plan for the flood regulation will be located in the North Pacific Division Office, Corps of Engineers, Portland, Oregon.

(b) Daily Requests for Project Outflows. Pursuant to the operating rules in the Flood Control Plan, the outflows from individual Canadian storage projects are specified on a day-to-day basis. Requests will be coordinated by telephone daily or on an as needed basis, by conference calls between members of the

Operating Committee or their representatives. The requests will normally prescribe the requested outflows as a mean daily discharge in cubic feet per second, for the 24-hour period from noon to noon of each day. Daily requests for project outflows will be documented by message dispatched on the Columbia Basin Telecommunications Circuit from the Corps of Engineers, in Portland, Oregon. Acknowledgment of the teletype request will be made by the Canadian authority by teletype message. The project outflows from Canadian projects will be determined by methods as agreed upon for the Hydrometeorological Reporting Network. Any modification of the documented daily request shall be agreed by the Operating Committee before being put into effect, and shall be documented by teletype immediately thereafter.

(3) Regulation During Winter Floods. Daily requests for project outflows from Canadian projects are normally confined to the flood control refill period. During periods of high winter flows in the Lower Columbia River, if a special regulation of Arrow storage becomes necessary to preserve the natural flood control storage effect, the outflows from Arrow will be regulated on a day-to-day basis in accordance with the requests of the U.S. Section of the Operating Committee. The requests for such regulation will be in accordance with procedures described above.

6. OPERATING LIMITS

A. Duncan Project

(1) Maximum outflow - 20,000 cfs through outlets
(2) Minimum average weekly outflow - 100 cfs
(3) Maximum rate of change in outflow - 4,000 cfs per day
(4) Normal full pool elevation 1,892.0 feet
(5) Normal minimum pool elevation - 1,794.2 feet.

B. Arrow Project

(1) Maximum outflow - Physical limits only
(2) Minimum average weekly outflow - 5,000 cfs
(3) Maximum rate of change in outflow - 25,000 cfs per day
(4) Normal full pool elevation - 1,444.0 feet
(5) Normal minimum pool elevation - 1,377.9 feet
(6) Advance notice for changes in outflow for:

(a) Drop in downstream level of:

1/2 foot	None
1 foot	1 hour
2 feet	2 hours
3 feet	24 hours

(b) Rise in downstream level of:

1/2 foot - None
1 foot - 1 hour
2 feet - 2 hours
3 feet - 7 hours, only if notice is received before 10:00 hours that day, otherwise 24-hour notice is required.

C. Mica Project

In accordance with the 1988-89 Assured Operating Plan, the Mica Project will be operated to the following monthly average target outflows specified in (2) below except as qualified in paragraphs 6C(3) through 6C(6).

(1) Variable Refill Curves

Variable Refill Curves (VRCs) shall be constructed based on a power discharge requirement as indicated in Exhibit 6 with a target 31 July Treaty storage content of 3,529.2 KSFD.

(2) Mica Project Operating Criteria

Mica Treaty outflows will be determined from the Target End-of-Period Treaty Storage Content or Target Average Outflow shown in the table below, except for the limitations or changes required by subsections 6C(3) through 6C(6).

Period	Target End-of-Period Treaty Storage Content (ksfd)	Target Average Outflow (cfs)	Arrow Reservoir Previous Period Storage AER Content (ksfd)	Mica Outflow (cfs)	Minimum Outflow (cfs)
August 1-15	3,456.2	---	---	---	10,000
August 16-31	3,529.2	---	0 - 2,500	30,000	10,000
September	3,529.2	---	0 - 2,300	30,000	10,000
October	---	10,000	0 - 3,200	27,000	10,000
November	3,122.2	---	0 - 3,200	32,000	10,000
December	---	28,000	0 - 3,200	34,000	15,000
January	---	28,000	0 - 2,800	34,000	15,000
February	---	23,000	0 - 600	28,000	15,000
March	---	17,000	0 - ---	---	15,000
April 1-15	---	15,000	0 - ---	---	15,000
April 16-30	---	10,000	0 - 300	20,000	10,000
May	---	10,000	0 - 350	20,000	10,000
June	---	10,000	0 - ---	---	10,000
July	3,356.2	---	0 - ---	---	10,000

(3) Mica operation to the Target End-of-Period Treaty Storage Contents shall be limited by the Minimum Outflows shown in the table above, and a maximum outflow of 34,000 cfs when the Target End-of-Period Storage Content is below 3529.2 ksfd.

(4) Mica outflows will be increased during the months October through June as required to avoid violation of the Flood Control Storage Reservation Curve.

(5) Mica outflows will be adjusted from the outflow necessary to meet the Target End-of-Period Treaty Storage Content or increased from the Target Average Outflow to the Mica Outflow shown in the table on the previous page when the Arrow Reservoir Previous Period Storage Content, as determined by the Actual Energy Regulation (AER) that is available just prior to the beginning of each month, is within the limits shown in the table, except when:

(a) the Variable Refill Curve for Arrow at any time during the period January through July is calculated according to the criteria specified in Subsection 3G(1), and

(b) the total Canadian Treaty storage is at or above the Operating Rule Curve.

(6) Storage releases from Mica in excess of 7 million acre-feet (MAF) that result from operating Mica under the criteria described in 6C(2) through 6C(5) above will be retained in the Arrow reservoir, subject to flood control criteria at Arrow, and Mica will be reduced to Minimum Outflow as required to minimize releases in excess of 7 MAF. The total combined storage draft from Mica and Arrow will not exceed 14.1 million acre-feet unless flood control criteria will not permit the additional Mica storage releases for minimum flow purposes to be retained at Arrow.

D. Libby Project

(1) Maximum Outflow - When the spillway capacity is insufficient to pass the required flow, the regulating outlets may be used.

Forebay Elevation	One Sluice	Three Sluices
2459 ft.	20,300 cfs	61,000 cfs
2425 ft.	19,000 cfs	57,000 cfs
2405 ft.	18,200 cfs	54,600 cfs
2350 ft.	15,500 cfs	46,500 cfs
2287 ft.	11,700 cfs	35,000 cfs

(2) Minimum instantaneous outflow, 2,000 cfs; for refill in critical years minimum daily outflow, 3,000 cfs; desirable minimum daily outflow, 4,000 cfs.

(3) Maximum rate of tailwater change
(a) May - September - 1 ft. per hour
4 ft. per 24 hours
(b) October - April - 1 ft. per 1/2 hour
6 ft. per 24 hours

(4) Maximum pool elevation - 2459.0 feet

(5) Minimum pool elevation - 2287.0 feet

DETAILED OPERATING PLAN FOR CANADIAN TREATY STORAGE
FIRST CRITICAL RULE CURVE AND ASSURED REFILL CURVE FOR 1988-89
End-of-Month Usable Storage Content in 1000 SFD

	Critical Rule Curve (1)				Assured Refill Curve (2)		
Month	Duncan	Arrow	Mica	Total	Duncan	Arrow	Mica
August 15	705.8	3579.6	3529.2	7814.6	25.6	0.0	982.1
August 31	705.8	3579.6	3529.2	7814.6	96.5	0.0	1453.5
September	697.3	3564.0	3529.2	7790.5	162.8	0.0	1846.5
October	693.8	3453.6	3428.4	7575.9	193.5	0.0	1807.8
November	705.8	3453.6	3122.2	7281.6	211.0	0.0	1663.0
December	504.1	3075.4	2381.8	5961.3	222.2	0.0	1307.4
January	343.5	1984.9	1644.1	3972.5	232.4	236.5	930.3
February	156.9	1585.2	1080.2	2822.3	241.6	824.7	582.8
March	165.8	1862.5	650.1	2678.4	255.7	1339.8	217.6
April 15	72.7	1056.9	455.3	1584.9	244.9	1363.8	62.8
April 30	81.1	779.6	359.0	1219.7	234.1	1512.7	21.2
May	198.6	1574.5	591.4	2364.5	341.7	2429.0	581.7
June	473.4	3328.9	2029.8	5832.1	531.6	3579.6	2088.0
July	660.3	3579.6	2970.1	7210.0	705.8	3579.6	3529.2

(1) Source: Pacific Northwest Coordination Agreement 1988-89 Final Regulation.

(2) The Assured Refill Curve indicates the end-of-month storage content required to assure refill of Canadian storage by 31 July based on 1931 historical monthly inflow. The monthly inflow at each reservoir is reduced by deducting the Power Discharge Requirement for an 80 MAF runoff at The Dalles and water required for refill, if any, at upstream reservoirs. The Power Discharge Requirement for each reservoir for the period January-July is defined in Exhibit 6.

Exhibit 2

DETAILED OPERATING PLAN FOR COLUMBIA RIVER TREATY STORAGE
SECOND CRITICAL RULE CURVE
1988-89
End-of-Month Usable Storage Content in 1000 SFD

Month	Duncan	Arrow	Mica	Total
August 15	676.2	3579.6	3456.2	7712.0
August 31	701.1	3570.5	3529.2	7800.8
September	573.7	3319.5	3529.2	7422.4
October	411.0	3099.1	3428.4	6938.5
November	193.9	3159.3	2585.7	5938.9
December	125.3	2821.5	1621.5	4568.3
January	118.4	1685.2	823.1	2626.7
February	122.7	1585.2	254.4	1962.3
March	131.1	1784.7	0.0	1915.8
April 15	43.3	879.6	0.0	922.9
April 30	77.2	779.6	0.0	856.8
May	191.9	1574.5	326.8	2093.2
June	302.9	2288.2	1683.7	4274.8
July	343.1	3082.9	2970.1	6396.1

Source: Second-year critical rule curves from the 1988-89 AOP Studies unless higher than the first-year critical rule curve.

DETAILED OPERATING PLAN FOR COLUMBIA RIVER TREATY STORAGE
THIRD CRITICAL RULE CURVE
1988-89
End-of-Month Usable Storage Content in 1000 SFD

Month	Duncan	Arrow	Mica	Total
August 15	392.9	3222.9	3456.2	7072.0
August 31	440.6	3447.4	3529.2	7417.2
September	474.2	3203.4	3529.2	7206.8
October	323.5	3042.9	3428.4	6794.8
November	169.5	3101.9	2585.7	5857.1
December	70.9	2655.8	1621.5	4348.2
January	81.1	1685.2	698.9	2465.2
February	3.6	1534.7	128.9	1667.2
March	4.5	1623.1	0.0	1627.6
April 15	0.0	650.5	0.0	650.5
April 30	0.7	174.4	0.0	175.1
May	157.5	1304.7	65.9	1528.1
June	161.3	1813.0	1437.9	3412.2
July	78.0	2274.0	2636.8	4688.8

Source: Third-year critical rule curves from the 1988-89 AOP Studies unless higher than the first or second-year critical rule curves.

DETAILED OPERATING PLAN FOR COLUMBIA RIVER TREATY STORAGE
FOURTH CRITICAL RULE CURVE
1988-89
End-of-Month Usable Storage Content in 1000 SFD

Month	Duncan	Arrow	Mica	Total
August 15	3.3	2114.6	3099.5	5217.4
August 31	0.5	2011.0	3186.3	5197.8
September	0.4	1856.2	3066.5	4923.1
October	1.8	1737.8	2552.5	4292.1
November	1.5	1313.2	1823.0	3137.7
December	0.0	304.9	910.8	1215.7
January	0.0	575.4	0.0	575.4
February	0.0	0.0	0.0	0.0

Source: Fourth-year critical rule curves from the 1988-89 AOP Study.

Exhibit 5

DETAILED OPERATING PLAN FOR COLUMBIA RIVER TREATY STORAGE
LIMITING RULE CURVE BASED ON 1936-37 HYDRO CONDITIONS
End-of-Month Usable Storage Contents in 1000 SFD

Month	Duncan	Arrow	Mica	Libby
January	1.1	624.1	316.1	226.9
February	1.5	245.9	1.2	197.9
March	0.8	181.2	1.2	51.1

Source: Pacific Northwest Coordinating Group Study dated August 28, 1987.

DETAILED OPERATING PLAN FOR COLUMBIA RIVER TREATY STORAGE
1988-89 VARIABLE REFILL CURVE PROCEDURES

The Variable Refill Curves indicate the end-of-month storage content required to refill Canadian storage based on forecasts of natural inflow volume. The probable forecast volume at each reservoir is reduced by deducting the 95 percent confidence forecast error, project discharge requirement, nonpower requirements upstream, and water required for refill at upstream reservoirs. Studies made for the U.S. Coordinated System Operation indicate that the Power Discharge Requirement for all cyclic reservoirs must be greater than project minimum release to allow filling in accordance with the Principles and Procedures coincident with carrying system firm load when the Columbia River at The Dalles natural January-July runoff volume is lower than 95 million acre-feet. The following schedule for Power Discharge Requirements will apply when computing the Variable Refill Curves during the period January 1 through June 1.

POWER DISCHARGE REQUIREMENT, IN CFS
FOR JANUARY-JULY VOLUME RUNOFF
OF THE COLUMBIA RIVER AT THE DALLES, OREGON

Project	Jan.	Feb.	Mar.	Apr. 1-15	Apr. 16-30	May	June	July
				80 MAF				
Mica	15,000	15,000	15,000	15,000	10,000	10,000	10,000	10,000
Arrow	5,000	5,000	5,000	22,000	22,000	31,000	31,000	48,000
Duncan	100	100	100	1,700	1,700	1,700	1,700	1,700
Libby 1/	4,000	4,000	4,000	9,000	10,000	10,000	10,000	10,000
				90 MAF				
Mica	Same as 80 MAF							
Arrow	5,000	5,000	5,000	9,600	9,600	9,600	26,500	29,000
Duncan	100	100	100	900	900	900	900	900
Libby 1/	4,000	4,000	4,000	6,500	7,000	7,000	7,000	7,000
				95 MAF and Higher				
Mica	Same as 80 MAF							
Arrow	5,000	5,000	5,000	5,000	5,000	5,000	14,000	14,000
Duncan	100	100	100	100	100	100	100	100
Libby 1/	4,000	4,000	4,000	4,000	4,000	4,000	4,000	4,000

If the forecasted natural January through July volume runoff at The Dalles is less than 80 MAF, the Power Discharge Requirement in the 80 MAF schedule will be used. For intermediate forecasted volumes, the Power Discharge Requirement will be interpolated linearly between the values shown above.

It is recognized that the Canadian Section has the right to make changes to the refill curves for individual projects provided the effect of these changes is consistent with the composite refill curve for Total Canadian storage.

1/ Data may be revised upon completion of U.S. Entity refill studies. The Canadian Entity reserves the right to request changes to the revised data.

CRITICAL RULE CURVES AND ENERGY CONTENT CURVE
LIBBY RESERVOIR
1988-89
End-of-Month Usable Storage Content in 1000 SFD

Month	Critical Rule Curve 1st	2nd	3rd	4th	Energy Content Curve 1/
August 15	2510.5	2508.3	2475.7	1225.6	2510.5
August 31	2510.5	2505.1	2448.2	1186.5	2510.5
September	2193.3	2487.3	2406.4	1109.1	2265.1
October	1819.5	2195.7	2148.5	829.9	2262.8
November	1180.8	1784.4	1766.9	678.7	2233.8
December	672.6	1404.2	1274.5	491.8	1501.9
January	634.2	938.4	938.4	163.5	1776.5
February	595.5	861.2	715.6	0.0	2052.0
March	405.3	837.5	698.1	0.0	2028.8
April 15	398.1	898.0	694.8	0.0	1938.1
April 30	415.2	1066.3	626.8	0.0	1845.2
May	927.6	1552.9	1102.6	0.0	2117.1
June	1929.1	2437.8	1564.6	0.0	2484.7
July	2268.3	2475.7	1361.7	0.0	2510.5

Source: First critical rule curve from Pacific Northwest Coordination Agreement 1988-89 final regulation. Second, third, and fourth critical rule curves from 1988-89 AOP Studies unless higher than first critical rule curve.

1/ Data may be revised upon completion of U.S. Entity refill studies. The Canadian Entity reserves the right to request changes to the revised data.

FIGURES IN 1000"S
OF SECOND FOOT DAYS

ELEVATION IN FEET	.0	.1	.2	.3	.4	.5	.6	.7	.8	.9	AVERAGE DIFFERENCE PER TENTH FT
1892.	705.8										
1891.	696.9	697.8	698.7	699.6	700.5	701.3	702.2	703.1	704.0	704.9	0.89
1890.	688.0	688.9	689.8	690.7	691.6	692.4	693.3	694.2	695.1	696.0	0.89
1889.	679.2	680.1	681.0	681.8	682.7	683.6	684.5	685.4	686.2	687.1	0.88
1888.	670.4	671.3	672.2	673.0	673.9	674.8	675.7	676.6	677.4	678.3	0.88
1887.	661.5	662.4	663.3	664.2	665.1	665.9	666.8	667.7	668.6	669.5	0.89
1886.	652.8	653.7	654.5	655.4	656.3	657.1	658.0	658.9	659.8	660.6	0.87
1885.	644.0	644.9	645.8	646.6	647.5	648.4	649.3	650.2	651.0	651.9	0.88
1884.	635.3	636.2	637.0	637.9	638.8	639.6	640.5	641.4	642.3	643.1	0.87
1883.	626.6	627.5	628.3	629.2	630.1	630.9	631.8	632.7	633.6	634.4	0.87
1882.	617.9	618.8	619.6	620.5	621.4	622.2	623.1	624.0	624.9	625.7	0.87
1881.	609.2	610.1	610.9	611.8	612.7	613.5	614.4	615.3	616.2	617.0	0.87
1880.	600.6	601.5	602.3	603.2	604.0	604.9	605.8	606.6	607.5	608.3	0.86
1879.	592.0	592.9	593.7	594.6	595.4	596.3	597.2	598.0	598.9	599.7	0.86
1878.	583.4	584.3	585.1	586.0	586.8	587.7	588.6	589.4	590.3	591.1	0.86
1877.	574.8	575.7	576.5	577.4	578.2	579.1	580.0	580.8	581.7	582.5	0.86
1876.	566.3	567.1	568.0	568.8	569.7	570.5	571.4	572.2	573.1	573.9	0.85
1875.	557.8	558.6	559.5	560.3	561.2	562.0	562.9	563.7	564.6	565.4	0.85
1874.	549.3	550.1	551.0	551.8	552.7	553.5	554.4	555.2	556.1	556.9	0.85
1873.	540.9	541.7	542.6	543.4	544.3	545.1	545.9	546.8	547.6	548.5	0.84
1872.	532.4	533.2	534.1	534.9	535.8	536.6	537.5	538.3	539.2	540.0	0.85
1871.	524.0	524.8	525.7	526.5	527.4	528.2	529.0	529.9	530.7	531.6	0.84
1870.	515.7	516.5	517.4	518.2	519.0	519.8	520.7	521.5	522.3	523.2	0.83

Exhibit 8

ELEVATION IN FEET	.0	.1	.2	.3	.4	.5	.6	.7	.8	.9	AVERAGE DIFFERENCE PER TENTH FT
1869.	507.3	508.1	509.0	509.8	510.7	511.5	512.3	513.2	514.0	514.9	0.84
1868.	499.0	499.8	500.7	501.5	502.3	503.1	504.0	504.8	505.6	506.5	0.83
1867.	490.7	491.5	492.4	493.2	494.0	494.8	495.7	496.5	497.3	498.2	0.83
1866.	482.4	483.2	484.1	484.9	485.7	486.5	487.4	488.2	489.0	489.9	0.83
1865.	474.2	475.0	475.8	476.7	477.5	478.3	479.1	479.9	480.8	481.6	0.82
1864.	466.0	466.8	467.6	468.5	469.3	470.1	470.9	471.7	472.6	473.4	0.82
1863.	457.8	458.6	459.4	460.3	461.1	461.9	462.7	463.5	464.4	465.2	0.82
1862.	449.7	450.5	451.3	452.1	452.9	453.7	454.6	455.4	456.2	457.0	0.81
1861.	441.6	442.4	443.2	444.0	444.8	445.6	446.5	447.3	448.1	448.9	0.81
1860.	433.5	434.3	435.1	435.9	436.7	437.5	438.4	439.2	440.0	440.8	0.81
1859.	425.4	426.2	427.0	427.8	428.6	429.4	430.3	431.1	431.9	432.7	0.81
1858.	417.4	418.2	419.0	419.8	420.6	421.4	422.2	423.0	423.8	424.6	0.80
1857.	409.4	410.2	411.0	411.8	412.6	413.4	414.2	415.0	415.8	416.6	0.80
1856.	401.4	402.2	403.0	403.8	404.6	405.4	406.2	407.0	407.8	408.6	0.80
1855.	393.5	394.3	395.1	395.9	396.7	397.4	398.2	399.0	399.8	400.6	0.79
1854.	385.6	386.4	387.2	388.0	388.8	389.5	390.3	391.1	391.9	392.7	0.79
1853.	377.7	378.5	379.3	380.1	380.9	381.6	382.4	383.2	384.0	384.8	0.79
1852.	369.9	370.7	371.5	372.2	373.0	373.8	374.6	375.4	376.1	376.9	0.78
1851.	362.1	362.9	363.7	364.4	365.2	366.0	366.8	367.6	368.3	369.1	0.78
1850.	354.3	355.1	355.9	356.6	357.4	358.2	359.0	359.8	360.5	361.3	0.78
1849.	346.6	347.4	348.1	348.9	349.7	350.4	351.2	352.0	352.8	353.5	0.77
1848.	338.9	339.7	340.4	341.2	342.0	342.7	343.5	344.3	345.1	345.8	0.77
1847.	331.2	332.0	332.7	333.5	334.3	335.0	335.8	336.6	337.4	338.1	0.77
1846.	323.6	324.4	325.1	325.9	326.6	327.4	328.2	328.9	329.7	330.4	0.76
1845.	316.0	316.8	317.5	318.3	319.0	319.8	320.6	321.3	322.1	322.8	0.76

ELEVATION IN FEET	.0	.1	.2	.3	.4	.5	.6	.7	.8	.9	AVERAGE DIFFERENCE PER TENTH FT
1844.	308.5	309.2	310.0	310.7	311.5	312.2	313.0	313.7	314.5	315.2	0.75
1843.	300.9	301.7	302.4	303.2	303.9	304.7	305.5	306.2	307.0	307.7	0.76
1842.	293.5	294.2	295.0	295.7	296.5	297.2	297.9	298.7	299.4	300.2	0.74
1841.	286.0	286.7	287.5	288.2	289.0	289.7	290.5	291.2	292.0	292.7	0.75
1840.	278.6	279.3	280.1	280.8	281.6	282.3	283.0	283.8	284.5	285.3	0.74
1839.	271.2	271.9	272.7	273.4	274.2	274.9	275.6	276.4	277.1	277.9	0.74
1838.	263.9	264.6	265.4	266.1	266.8	267.5	268.3	269.0	269.7	270.5	0.73
1837.	256.6	257.3	258.1	258.8	259.5	260.2	261.0	261.7	262.4	263.2	0.73
1836.	249.4	250.1	250.8	251.6	252.3	253.0	253.7	254.4	255.2	255.9	0.72
1835.	242.2	242.9	243.6	244.4	245.1	245.8	246.5	247.2	248.0	248.7	0.72
1834.	235.0	235.7	236.4	237.2	237.9	238.6	239.3	240.0	240.8	241.5	0.72
1833.	227.9	228.6	229.3	230.0	230.7	231.4	232.2	232.9	233.6	234.3	0.71
1832.	220.8	221.5	222.2	222.9	223.6	224.3	225.1	225.8	226.5	227.2	0.71
1831.	213.8	214.5	215.2	215.9	216.6	217.3	218.0	218.7	219.4	220.1	0.70
1830.	206.8	207.5	208.2	208.9	209.6	210.3	211.0	211.7	212.4	213.1	0.70
1829.	199.9	200.6	201.3	202.0	202.7	203.3	204.0	204.7	205.4	206.1	0.69
1828.	193.0	193.7	194.4	195.1	195.8	196.4	197.1	197.8	198.5	199.2	0.69
1827.	186.1	186.8	187.5	188.2	188.9	189.5	190.2	190.9	191.6	192.3	0.69
1826.	179.3	180.0	180.7	181.3	182.0	182.7	183.4	184.1	184.7	185.4	0.68
1825.	172.6	173.3	173.9	174.6	175.3	175.9	176.6	177.3	178.0	178.6	0.67
1824.	165.9	166.6	167.2	167.9	168.6	169.2	169.9	170.6	171.3	171.9	0.67
1823.	159.2	159.9	160.5	161.2	161.9	162.5	163.2	163.9	164.6	165.2	0.67
1822.	152.6	153.3	153.9	154.6	155.2	155.9	156.6	157.2	157.9	158.5	0.66
1821.	146.1	146.7	147.4	148.0	148.7	149.3	150.0	150.6	151.3	151.9	0.65
1820.	139.6	140.2	140.9	141.5	142.2	142.8	143.5	144.1	144.8	145.4	0.65

ELEVATION IN FEET	.0	.1	.2	.3	.4	.5	.6	.7	.8	.9	AVERAGE DIFFERENCE PER TENTH FT
1819.	133.2	133.8	134.5	135.1	135.8	136.4	137.0	137.7	138.3	139.0	0.64
1818.	126.8	127.4	128.1	128.7	129.4	130.0	130.6	131.3	131.9	132.6	0.64
1817.	120.5	121.1	121.8	122.4	123.0	123.6	124.3	124.9	125.5	126.2	0.63
1816.	114.3	114.9	115.5	116.2	116.8	117.4	118.0	118.6	119.3	119.9	0.62
1815.	108.1	108.7	109.3	110.0	110.6	111.2	111.8	112.4	113.1	113.7	0.62
1814.	102.0	102.6	103.2	103.8	104.4	105.0	105.7	106.3	106.9	107.5	0.61
1813.	96.0	96.6	97.2	97.8	98.4	99.0	99.6	100.2	100.8	101.4	0.60
1812.	90.0	90.6	91.2	91.8	92.4	93.0	93.6	94.2	94.8	95.4	0.60
1811.	84.1	84.7	85.3	85.9	86.5	87.0	87.6	88.2	88.8	89.4	0.59
1810.	78.3	78.9	79.5	80.0	80.6	81.2	81.8	82.4	82.9	83.5	0.58
1809.	72.5	73.1	73.7	74.2	74.8	75.4	76.0	76.6	77.1	77.7	0.58
1808.	66.9	67.5	68.0	68.6	69.1	69.7	70.3	70.8	71.4	71.9	0.56
1807.	61.3	61.9	62.4	63.0	63.5	64.1	64.7	65.2	65.8	66.3	0.56
1806.	55.8	56.3	56.9	57.4	58.0	58.5	59.1	59.6	60.2	60.7	0.55
1805.	50.4	50.9	51.5	52.0	52.6	53.1	53.6	54.2	54.7	55.3	0.54
1804.	45.1	45.6	46.2	46.7	47.2	47.7	48.3	48.8	49.3	49.9	0.53
1803.	39.9	40.4	40.9	41.5	42.0	42.5	43.0	43.5	44.1	44.6	0.52
1802.	34.8	35.3	35.8	36.3	36.8	37.3	37.9	38.4	38.9	39.4	0.51
1801.	29.8	30.3	30.8	31.3	31.8	32.3	32.8	33.3	33.8	34.3	0.50
1800.	25.0	25.5	26.0	26.4	26.9	27.4	27.9	28.4	28.8	29.3	0.48
1799.	20.3	20.8	21.2	21.7	22.2	22.6	23.1	23.6	24.1	24.5	0.47
1798.	15.7	16.2	16.6	17.1	17.5	18.0	18.5	18.9	19.4	19.8	0.46
1797.	11.3	11.7	12.2	12.6	13.1	13.5	13.9	14.4	14.8	15.3	0.44
1796.	7.1	7.5	7.9	8.4	8.8	9.2	9.6	10.0	10.5	10.9	0.42
1795.	3.0	3.4	3.8	4.2	4.6	5.0	5.5	5.9	6.3	6.7	0.41
1794.			0.0	0.4	0.8	1.1	1.5	1.9	2.3	2.6	0.37

FIGURES IN 1000"S
OF SECOND FOOT DAYS

ELEVATION IN FEET	.0	.1	.2	.3	.4	.5	.6	.7	.8	.9	AVERAGE DIFFERENCE PER TENTH FT
1444.	3579.6										
1443.	3514.1	3520.6	3527.2	3533.7	3540.3	3546.8	3553.4	3559.9	3566.5	3573.0	6.55
1442.	3448.9	3455.4	3461.9	3468.5	3475.0	3481.5	3488.0	3494.5	3501.1	3507.6	6.52
1441.	3384.0	3390.5	3397.0	3403.5	3410.0	3416.4	3422.9	3429.4	3435.9	3442.4	6.49
1440.	3319.5	3325.9	3332.4	3338.8	3345.3	3351.7	3358.2	3364.6	3371.1	3377.5	6.45
1439.	3255.2	3261.6	3268.1	3274.5	3280.9	3287.3	3293.8	3300.2	3306.6	3313.1	6.43
1438.	3191.4	3197.8	3204.2	3210.5	3216.9	3223.3	3229.7	3236.1	3242.4	3248.8	6.38
1437.	3127.8	3134.2	3140.5	3146.9	3153.2	3159.6	3166.0	3172.3	3178.7	3185.0	6.36
1436.	3064.6	3070.9	3077.2	3083.6	3089.9	3096.2	3102.5	3108.8	3115.2	3121.5	6.32
1435.	3001.7	3008.0	3014.3	3020.6	3026.9	3033.1	3039.4	3045.7	3052.0	3058.3	6.29
1434.	2939.2	2945.4	2951.7	2957.9	2964.2	2970.4	2976.7	2982.9	2989.2	2995.4	6.25
1433.	2877.0	2883.2	2889.4	2895.7	2901.9	2908.1	2914.3	2920.5	2926.8	2933.0	6.22
1432.	2815.1	2821.3	2827.5	2833.7	2839.9	2846.0	2852.2	2858.4	2864.6	2870.8	6.19
1431.	2753.5	2759.7	2765.8	2772.0	2778.1	2784.3	2790.5	2796.6	2802.8	2808.9	6.16
1430.	2692.3	2698.4	2704.5	2710.7	2716.8	2722.9	2729.0	2735.1	2741.3	2747.4	6.12
1429.	2631.5	2637.6	2643.7	2649.7	2655.8	2661.9	2668.0	2674.1	2680.1	2686.2	6.08
1428.	2570.9	2577.0	2583.0	2589.1	2595.1	2601.2	2607.3	2613.3	2619.4	2625.4	6.06
1427.	2510.7	2516.7	2522.7	2528.8	2534.8	2540.8	2546.8	2552.8	2558.9	2564.9	6.02
1426.	2450.8	2456.8	2462.8	2468.8	2474.8	2480.7	2486.7	2492.7	2498.7	2504.7	5.99
1425.	2391.2	2397.2	2403.1	2409.1	2415.0	2421.0	2427.0	2432.9	2438.9	2444.8	5.96
1424.	2331.9	2337.8	2343.8	2349.7	2355.6	2361.5	2367.5	2373.4	2379.3	2385.3	5.93
1423.	2272.8	2278.7	2284.6	2290.5	2296.4	2302.3	2308.3	2314.2	2320.1	2326.0	5.91
1422.	2214.1	2220.0	2225.8	2231.7	2237.6	2243.4	2249.3	2255.2	2261.1	2266.9	5.87
1421.	2155.7	2161.5	2167.4	2173.2	2179.1	2184.9	2190.7	2196.6	2202.4	2208.3	5.84
1420.	2097.7	2103.5	2109.3	2115.1	2120.9	2126.7	2132.5	2138.3	2144.1	2149.9	5.80

Exhibit 9

ELEVATION IN FEET	.0	.1	.2	.3	.4	.5	.6	.7	.8	.9	AVERAGE DIFFERENCE PER TENTH FT
1419.	2040.1	2045.9	2051.6	2057.4	2063.1	2068.9	2074.7	2080.4	2086.2	2091.9	5.76
1418.	1982.9	1988.6	1994.3	2000.1	2005.8	2011.5	2017.2	2022.9	2028.7	2034.4	5.72
1417.	1926.1	1931.8	1937.5	1943.1	1948.8	1954.5	1960.2	1965.9	1971.5	1977.2	5.68
1416.	1869.6	1875.2	1880.9	1886.5	1892.2	1897.8	1903.5	1909.1	1914.8	1920.4	5.65
1415.	1813.5	1819.1	1824.7	1830.3	1835.9	1841.5	1847.2	1852.8	1858.4	1864.0	5.61
1414.	1757.8	1763.4	1768.9	1774.5	1780.1	1785.6	1791.2	1796.8	1802.4	1807.9	5.57
1413.	1702.4	1707.9	1713.5	1719.0	1724.6	1730.1	1735.6	1741.2	1746.7	1752.3	5.54
1412.	1647.4	1652.9	1658.4	1663.9	1669.4	1674.9	1680.4	1685.9	1691.4	1696.9	5.50
1411.	1592.7	1598.2	1603.6	1609.1	1614.6	1620.0	1625.5	1631.0	1636.5	1641.9	5.47
1410.	1538.4	1543.8	1549.3	1554.7	1560.1	1565.5	1571.0	1576.4	1581.8	1587.3	5.43
1409.	1484.5	1489.9	1495.3	1500.7	1506.1	1511.4	1516.8	1522.2	1527.6	1533.0	5.39
1408.	1430.9	1436.3	1441.6	1447.0	1452.3	1457.7	1463.1	1468.4	1473.8	1479.1	5.36
1407.	1377.7	1383.0	1388.3	1393.7	1399.0	1404.3	1409.6	1414.9	1420.3	1425.6	5.32
1406.	1324.7	1330.0	1335.3	1340.6	1345.9	1351.2	1356.5	1361.8	1367.1	1372.4	5.30
1405.	1272.1	1277.4	1282.6	1287.9	1293.1	1298.4	1303.7	1308.9	1314.2	1319.4	5.26
1404.	1219.5	1224.8	1230.0	1235.3	1240.5	1245.8	1251.1	1256.3	1261.6	1266.8	5.26
1403.	1167.3	1172.5	1177.7	1183.0	1188.2	1193.4	1198.6	1203.8	1209.1	1214.3	5.22
1402.	1115.4	1120.6	1125.8	1131.0	1136.2	1141.3	1146.5	1151.7	1156.9	1162.1	5.19
1401.	1063.9	1069.0	1074.2	1079.3	1084.5	1089.6	1094.8	1099.9	1105.1	1110.2	5.15
1400.	1012.8	1017.9	1023.0	1028.1	1033.2	1038.3	1043.5	1048.6	1053.7	1058.8	5.11
1399.	962.5	967.5	972.6	977.6	982.6	987.6	992.7	997.7	1002.7	1007.8	5.03
1398.	912.7	917.7	922.7	927.6	932.6	937.6	942.6	947.6	952.5	957.5	4.98
1397.	863.2	868.1	873.1	878.0	883.0	887.9	892.9	897.8	902.8	907.7	4.95
1396.	814.1	819.0	823.9	828.8	833.7	838.6	843.6	848.5	853.4	858.3	4.91
1395.	765.2	770.1	775.0	779.9	784.8	789.6	794.5	799.4	804.3	809.2	4.89

ELEVATION IN FEET	.0	.1	.2	.3	.4	.5	.6	.7	.8	.9	AVERAGE DIFFERENCE PER TENTH FT
1394.	716.2	721.1	726.0	730.9	735.8	740.7	745.6	750.5	755.4	760.3	4.90
1393.	667.5	672.4	677.2	682.1	687.0	691.8	696.7	701.6	706.5	711.3	4.87
1392.	619.3	624.1	628.9	633.8	638.6	643.4	648.2	653.0	657.9	662.7	4.82
1391.	571.5	576.3	581.1	585.8	590.6	595.4	600.2	605.0	609.7	614.5	4.78
1390.	524.2	528.9	533.7	538.4	543.1	547.8	552.6	557.3	562.0	566.8	4.73
1389.	477.9	482.5	487.2	491.8	496.4	501.0	505.7	510.3	514.9	519.6	4.63
1388.	432.3	436.9	441.4	446.0	450.5	455.1	459.7	464.2	468.8	473.3	4.56
1387.	387.2	391.7	396.2	400.7	405.2	409.7	414.3	418.8	423.3	427.8	4.51
1386.	342.6	347.1	351.5	356.0	360.4	364.9	369.4	373.8	378.3	382.7	4.46
1385.	298.5	302.9	307.3	311.7	316.1	320.5	325.0	329.4	333.8	338.2	4.41
1384.	254.6	259.0	263.4	267.8	272.2	276.5	280.9	285.3	289.7	294.1	4.39
1383.	211.2	215.5	219.9	224.2	228.6	232.9	237.2	241.6	245.9	250.3	4.34
1382.	168.4	172.7	177.0	181.2	185.5	189.8	194.1	198.4	202.6	206.9	4.28
1381.	126.1	130.3	134.6	138.8	143.0	147.2	151.5	155.7	159.9	164.2	4.23
1380.	84.3	88.5	92.7	96.8	101.0	105.2	109.4	113.6	117.7	121.9	4.18
1379.	43.2	47.3	51.4	55.5	59.6	63.7	67.9	72.0	76.1	80.2	4.11
1378.	2.7	6.7	10.8	14.8	18.9	22.9	27.0	31.0	35.1	39.1	4.05
1377.										0.0	2.70

MICA RESERVOIR CAPACITY TABLE PAGE # 1

FIGURES IN 1000"S
OF SECOND FOOT DAYS

ELEVATION IN FEET	.0	.1	.2	.3	.4	.5	.6	.7	.8	.9	AVERAGE DIFFERENCE PER TENTH FT
2475.	10121.1										5.38
2474.	10067.5	10072.9	10078.2	10083.6	10088.9	10094.3	10099.7	10105.0	10110.4	10115.7	5.36
2473.	10014.1	10019.4	10024.8	10030.1	10035.5	10040.8	10046.1	10051.5	10056.8	10062.2	5.34
2472.	9960.8	9966.1	9971.5	9976.8	9982.1	9987.4	9992.8	9998.1	10003.4	10008.8	5.33
2471.	9907.8	9913.1	9918.4	9923.7	9929.0	9934.3	9939.6	9944.9	9950.2	9955.5	5.30
2470.	9854.8	9860.1	9865.4	9870.7	9876.0	9881.3	9886.6	9891.9	9897.2	9902.5	5.30
2469.	9802.1	9807.4	9812.6	9817.9	9823.2	9828.4	9833.7	9839.0	9844.3	9849.5	5.27
2468.	9749.5	9754.8	9760.0	9765.3	9770.5	9775.8	9781.1	9786.3	9791.6	9796.8	5.26
2467.	9697.1	9702.3	9707.6	9712.8	9718.1	9723.3	9728.5	9733.8	9739.0	9744.3	5.24
2466.	9644.8	9650.0	9655.3	9660.5	9665.7	9670.9	9676.2	9681.4	9686.6	9691.9	5.23
2465.	9592.7	9597.9	9603.1	9608.3	9613.5	9618.7	9624.0	9629.2	9634.4	9639.6	5.21
2464.	9540.8	9546.0	9551.2	9556.4	9561.6	9566.7	9571.9	9577.1	9582.3	9587.5	5.19
2463.	9489.0	9494.2	9499.4	9504.5	9509.7	9514.9	9520.1	9525.3	9530.4	9535.6	5.18
2462.	9437.4	9442.6	9447.7	9452.9	9458.0	9463.2	9468.4	9473.5	9478.7	9483.8	5.16
2461.	9386.0	9391.1	9396.3	9401.4	9406.6	9411.7	9416.8	9422.0	9427.1	9432.3	5.14
2460.	9334.8	9339.9	9345.0	9350.2	9355.3	9360.4	9365.5	9370.6	9375.8	9380.9	5.12
2459.	9283.7	9288.8	9293.9	9299.0	9304.1	9309.2	9314.4	9319.5	9324.6	9329.7	5.11
2458.	9232.8	9237.9	9243.0	9248.1	9253.2	9258.2	9263.3	9268.4	9273.5	9278.6	5.09
2457.	9182.0	9187.1	9192.2	9197.2	9202.3	9207.4	9212.5	9217.6	9222.6	9227.7	5.08
2456.	9131.4	9136.5	9141.5	9146.6	9151.6	9156.7	9161.8	9166.8	9171.9	9176.9	5.06
2455.	9081.0	9086.0	9091.1	9096.1	9101.2	9106.2	9111.2	9116.3	9121.3	9126.4	5.04

Exhibit 10

ELEVATION IN FEET	.0	.1	.2	.3	.4	.5	.6	.7	.8	.9	AVERAGE DIFFERENCE PER TENTH FT
2454.	9030.8	9035.8	9040.8	9045.9	9050.9	9055.9	9060.9	9065.9	9071.0	9076.0	5.02
2453.	8980.7	8985.7	8990.7	8995.7	9000.7	9005.7	9010.8	9015.8	9020.8	9025.8	5.01
2452.	8930.8	8935.8	8940.8	8945.8	8950.8	8955.7	8960.7	8965.7	8970.7	8975.7	4.99
2451.	8881.0	8886.0	8891.0	8895.9	8900.9	8905.9	8910.9	8915.9	8920.8	8925.8	4.98
2450.	8831.4	8836.4	8841.3	8846.3	8851.2	8856.2	8861.2	8866.1	8871.1	8876.0	4.96
2449.	8782.0	8786.9	8791.9	8796.8	8801.8	8806.7	8811.6	8816.6	8821.5	8826.5	4.94
2448.	8732.8	8737.7	8742.6	8747.6	8752.5	8757.4	8762.3	8767.2	8772.2	8777.1	4.92
2447.	8683.7	8688.6	8693.5	8698.4	8703.3	8708.2	8713.2	8718.1	8723.0	8727.9	4.91
2446.	8634.8	8639.7	8644.6	8649.5	8654.4	8659.2	8664.1	8669.0	8673.9	8678.8	4.89
2445.	8586.0	8590.9	8595.8	8600.6	8605.5	8610.4	8615.3	8620.2	8625.0	8629.9	4.88
2444.	8537.5	8542.3	8547.2	8552.0	8556.9	8561.7	8566.6	8571.4	8576.3	8581.1	4.85
2443.	8489.1	8493.9	8498.8	8503.6	8508.5	8513.3	8518.1	8523.0	8527.8	8532.7	4.84
2442.	8440.8	8445.6	8450.5	8455.3	8460.1	8464.9	8469.8	8474.6	8479.4	8484.3	4.83
2441.	8392.7	8397.5	8402.3	8407.1	8411.9	8416.7	8421.6	8426.4	8431.2	8436.0	4.81
2440.	8344.8	8349.6	8354.4	8359.2	8364.0	8368.7	8373.5	8378.3	8383.1	8387.9	4.79
2439.	8297.1	8301.9	8306.6	8311.4	8316.2	8320.9	8325.7	8330.5	8335.3	8340.0	4.77
2438.	8249.5	8254.3	8259.0	8263.8	8268.5	8273.3	8278.1	8282.8	8287.6	8292.3	4.76
2437.	8202.1	8206.8	8211.6	8216.3	8221.1	8225.8	8230.5	8235.3	8240.0	8244.8	4.74
2436.	8154.8	8159.5	8164.3	8169.0	8173.7	8178.4	8183.2	8187.9	8192.6	8197.4	4.73
2435.	8107.8	8112.5	8117.2	8121.9	8126.6	8131.3	8136.0	8140.7	8145.4	8150.1	4.70
2434.	8060.9	8065.6	8070.3	8075.0	8079.7	8084.3	8089.0	8093.7	8098.4	8103.1	4.69
2433.	8014.1	8018.8	8023.5	8028.1	8032.8	8037.5	8042.2	8046.9	8051.5	8056.2	4.68
2432.	7967.5	7972.2	7976.8	7981.5	7986.1	7990.8	7995.5	8000.1	8004.8	8009.4	4.66
2431.	7921.1	7925.7	7930.4	7935.0	7939.7	7944.3	7948.9	7953.6	7958.2	7962.9	4.64
2430.	7874.9	7879.5	7884.1	7888.8	7893.4	7898.0	7902.6	7907.2	7911.9	7916.5	4.62

ELEVATION IN FEET	.0	.1	.2	.3	.4	.5	.6	.7	.8	.9	AVERAGE DIFFERENCE PER TENTH FT
2429.	7828.8	7833.4	7838.0	7842.6	7847.2	7851.8	7856.5	7861.1	7865.7	7870.3	4.61
2428.	7782.9	7787.5	7792.1	7796.7	7801.3	7805.8	7810.4	7815.0	7819.6	7824.2	4.59
2427.	7737.2	7741.8	7746.3	7750.9	7755.5	7760.0	7764.6	7769.2	7773.8	7778.3	4.57
2426.	7691.6	7696.2	7700.7	7705.3	7709.8	7714.4	7719.0	7723.5	7728.1	7732.6	4.56
2425.	7646.2	7650.7	7655.3	7659.8	7664.4	7668.9	7673.4	7678.0	7682.5	7687.1	4.54
2424.	7600.9	7605.4	7610.0	7614.5	7619.0	7623.5	7628.1	7632.6	7637.1	7641.7	4.53
2423.	7555.9	7560.4	7564.9	7569.4	7573.9	7578.4	7582.9	7587.4	7591.9	7596.4	4.50
2422.	7511.0	7515.5	7520.0	7524.5	7529.0	7533.4	7537.9	7542.4	7546.9	7551.4	4.49
2421.	7466.2	7470.7	7475.2	7479.6	7484.1	7488.6	7493.1	7497.6	7502.0	7506.5	4.48
2420.	7421.6	7426.1	7430.5	7435.0	7439.4	7443.9	7448.4	7452.8	7457.3	7461.7	4.46
2419.	7377.2	7381.6	7386.1	7390.5	7395.0	7399.4	7403.8	7408.3	7412.7	7417.2	4.44
2418.	7333.0	7337.4	7341.8	7346.3	7350.7	7355.1	7359.5	7363.9	7368.4	7372.8	4.42
2417.	7288.9	7293.3	7297.7	7302.1	7306.5	7310.9	7315.4	7319.8	7324.2	7328.6	4.41
2416.	7245.0	7249.4	7253.8	7258.2	7262.6	7266.9	7271.3	7275.7	7280.1	7284.5	4.39
2415.	7201.3	7205.7	7210.0	7214.4	7218.8	7223.1	7227.5	7231.9	7236.3	7240.6	4.37
2414.	7157.7	7162.1	7166.4	7170.8	7175.1	7179.5	7183.9	7188.2	7192.6	7196.9	4.36
2413.	7114.3	7118.6	7123.0	7127.3	7131.7	7136.0	7140.3	7144.7	7149.0	7153.4	4.34
2412.	7071.0	7075.3	7079.7	7084.0	7088.3	7092.6	7097.0	7101.3	7105.6	7110.0	4.33
2411.	7028.0	7032.3	7036.6	7040.9	7045.2	7049.5	7053.8	7058.1	7062.4	7066.7	4.30
2410.	6985.1	6989.4	6993.7	6998.0	7002.3	7006.5	7010.8	7015.1	7019.4	7023.7	4.29
2409.	6942.3	6946.6	6950.9	6955.1	6959.4	6963.7	6968.0	6972.3	6976.5	6980.8	4.28
2408.	6899.7	6904.0	6908.2	6912.5	6916.7	6921.0	6925.3	6929.5	6933.8	6938.0	4.26
2407.	6857.3	6861.5	6865.8	6870.0	6874.3	6878.5	6882.7	6887.0	6891.2	6895.5	4.24
2406.	6815.1	6819.3	6823.5	6827.8	6832.0	6836.2	6840.4	6844.6	6848.9	6853.1	4.22
2405.	6773.0	6777.2	6781.4	6785.6	6789.8	6794.0	6798.3	6802.5	6806.7	6810.9	4.21

ELEVATION IN FEET	.0	.1	.2	.3	.4	.5	.6	.7	.8	.9	AVERAGE DIFFERENCE PER TENTH FT
2404.	6731.1	6735.3	6739.5	6743.7	6747.9	6752.0	6756.2	6760.4	6764.6	6768.8	4.19
2403.	6689.4	6693.6	6697.7	6701.9	6706.1	6710.2	6714.4	6718.6	6722.8	6726.9	4.17
2402.	6647.8	6652.0	6656.1	6660.3	6664.4	6668.6	6672.8	6676.9	6681.1	6685.2	4.16
2401.	6606.4	6610.5	6614.7	6618.8	6623.0	6627.1	6631.2	6635.4	6639.5	6643.7	4.14
2400.	6565.1	6569.2	6573.4	6577.5	6581.6	6585.7	6589.9	6594.0	6598.1	6602.3	4.13
2399.	6524.1	6528.2	6532.3	6536.4	6540.5	6544.6	6548.7	6552.8	6556.9	6561.0	4.10
2398.	6483.4	6487.5	6491.5	6495.6	6499.7	6503.7	6507.8	6511.9	6516.0	6520.0	4.07
2397.	6443.0	6447.0	6451.1	6455.1	6459.2	6463.2	6467.2	6471.3	6475.3	6479.4	4.04
2396.	6403.0	6407.0	6411.0	6415.0	6419.0	6423.0	6427.0	6431.0	6435.0	6439.0	4.00
2395.	6363.4	6367.4	6371.3	6375.3	6379.2	6383.2	6387.2	6391.1	6395.1	6399.0	3.95
2394.	6324.1	6328.0	6332.0	6335.9	6339.8	6345.7	6347.7	6351.6	6355.5	6359.5	3.93
2393.	6285.1	6289.0	6292.9	6295.8	6300.7	6304.6	6308.5	6312.4	6316.3	6320.2	3.90
2392.	6240.4	6250.3	6254.1	6258.0	6261.9	6265.7	6269.6	6273.5	6277.4	6281.2	3.87
2391.	6208.1	6211.9	6215.8	6219.6	6223.4	6227.2	6231.1	6234.9	6238.7	6242.6	3.83
2390.	6170.1	6173.9	6177.7	6181.5	6185.3	6189.1	6192.9	6196.7	6200.5	6204.3	3.80

LIBBY RESERVOIR CAPACITY TABLE PAGE # 1

FIGURES IN 1000"S OF SECOND FOOT DAYS

TOP ELEVATION 2459.0 FT.
BOTTOM ELEVATION 2287.0 FT.
USABLE STORAGE 2510.5 KSFD

H/K = 107.80
FED H/K = 81.00

ELEVATION IN FEET	.0	.1	.2	.3	.4	.5	.6	.7	.8	.9	AVERAGE DIFFERENCE PER TENTH FT
2459.	2510.5										
2458.	2487.1	2489.4	2491.8	2494.1	2496.5	2498.8	2501.1	2503.5	2505.8	2508.2	2.34
2457.	2463.8	2466.1	2468.5	2470.8	2473.1	2475.4	2477.8	2480.1	2482.4	2484.8	2.33
2456.	2440.6	2442.9	2445.2	2447.6	2449.9	2452.2	2454.5	2456.8	2459.2	2461.5	2.32
2455.	2417.5	2419.8	2422.1	2424.4	2426.7	2429.0	2431.4	2433.7	2436.0	2438.3	2.31
2454.	2394.5	2396.8	2399.1	2401.4	2403.7	2406.0	2408.3	2410.6	2412.9	2415.2	2.30
2453.	2371.6	2373.9	2376.2	2378.5	2380.8	2383.0	2385.3	2387.6	2389.9	2392.2	2.29
2452.	2348.8	2351.1	2353.4	2355.6	2357.9	2360.2	2362.5	2364.8	2367.0	2369.3	2.28
2451.	2326.1	2328.4	2330.6	2332.9	2335.2	2337.4	2339.7	2342.0	2344.3	2346.5	2.27
2450.	2303.4	2305.7	2307.9	2310.2	2312.5	2314.7	2317.0	2319.3	2321.6	2323.8	2.27
2449.	2280.9	2283.1	2285.4	2287.6	2289.9	2292.1	2294.4	2296.6	2298.9	2301.1	2.25
2448.	2258.4	2260.6	2262.9	2265.1	2267.4	2269.6	2271.9	2274.1	2276.4	2278.6	2.25
2447.	2236.1	2238.3	2240.6	2242.8	2245.0	2247.2	2249.5	2251.7	2253.9	2256.2	2.23
2446.	2213.8	2216.0	2218.3	2220.5	2222.7	2224.9	2227.2	2229.4	2231.6	2233.9	2.23
2445.	2191.7	2193.9	2196.1	2198.3	2200.5	2202.7	2205.0	2207.2	2209.4	2211.6	2.21
2444.	2170.0	2172.2	2174.3	2176.5	2178.7	2180.8	2183.0	2185.2	2187.4	2189.5	2.17
2443.	2147.7	2149.9	2152.2	2154.4	2156.6	2158.8	2161.1	2163.3	2165.5	2167.8	2.23
2442.	2125.9	2128.1	2130.3	2132.4	2134.6	2136.8	2139.0	2141.2	2143.3	2145.5	2.18
2441.	2104.1	2106.3	2108.5	2110.6	2112.8	2115.0	2117.2	2119.4	2121.5	2123.7	2.18
2440.	2082.5	2084.7	2086.8	2089.0	2091.1	2093.3	2095.5	2097.6	2099.8	2101.9	2.16
2439.	2061.0	2063.1	2065.3	2067.4	2069.6	2071.7	2073.9	2076.0	2078.2	2080.3	2.15
2438.	2039.5	2041.6	2043.8	2045.9	2048.1	2050.2	2052.4	2054.5	2056.7	2058.8	2.15
2437.	2018.2	2020.3	2022.5	2024.6	2026.7	2028.8	2031.0	2033.1	2035.2	2037.4	2.13
2436.	1997.0	1999.1	2001.2	2003.4	2005.5	2007.6	2009.7	2011.8	2014.0	2016.1	2.12
2435.	1975.9	1978.0	1980.1	1982.2	1984.3	1986.4	1988.6	1990.7	1992.8	1994.9	2.11

Exhibit 11

ELEVATION IN FEET	.0	.1	.2	.3	.4	.5	.6	.7	.8	.9	AVERAGE DIFFERENCE PER TENTH FT
2434.	1954.9	1957.0	1959.1	1961.2	1963.3	1965.4	1967.5	1969.6	1971.7	1973.8	2.10
2433.	1934.0	1936.1	1938.2	1940.3	1942.4	1944.4	1946.5	1948.6	1950.7	1952.8	2.09
2432.	1913.2	1915.3	1917.4	1919.4	1921.5	1923.6	1925.7	1927.8	1929.8	1931.9	2.08
2431.	1892.5	1894.6	1896.6	1898.7	1900.8	1902.8	1904.9	1907.0	1909.1	1911.1	2.07
2430.	1871.9	1874.0	1876.0	1878.1	1880.1	1882.2	1884.3	1886.3	1888.4	1890.4	2.06
2429.	1851.4	1853.4	1855.5	1857.5	1859.6	1861.6	1863.7	1865.7	1867.8	1869.8	2.05
2428.	1831.0	1833.0	1835.1	1837.1	1839.2	1841.2	1843.2	1845.3	1847.3	1849.4	2.04
2427.	1810.7	1812.7	1814.8	1816.8	1818.8	1820.8	1822.9	1824.9	1826.9	1829.0	2.03
2426.	1790.6	1792.6	1794.6	1796.6	1798.6	1800.6	1802.7	1804.7	1806.7	1808.7	2.01
2425.	1770.5	1772.5	1774.5	1776.5	1778.5	1780.5	1782.6	1784.6	1786.6	1788.6	2.01
2424.	1750.6	1752.6	1754.6	1756.6	1758.6	1760.5	1762.5	1764.5	1766.5	1768.5	1.99
2423.	1730.8	1732.8	1734.8	1736.7	1738.7	1740.7	1742.7	1744.7	1746.6	1748.6	1.98
2422.	1711.1	1713.1	1715.0	1717.0	1719.0	1720.9	1722.9	1724.9	1726.9	1728.8	1.97
2421.	1691.5	1693.5	1695.4	1697.4	1699.3	1701.3	1703.3	1705.2	1707.2	1709.1	1.96
2420.	1672.0	1673.9	1675.9	1677.8	1679.8	1681.7	1683.7	1685.6	1687.6	1689.5	1.95
2419.	1652.6	1654.5	1656.5	1658.4	1660.4	1662.3	1664.2	1666.2	1668.1	1670.1	1.94
2418.	1633.3	1635.2	1637.2	1639.1	1641.0	1642.9	1644.9	1646.8	1648.7	1650.7	1.93
2417.	1614.2	1616.1	1618.0	1619.9	1621.8	1623.7	1625.7	1627.6	1629.5	1631.4	1.91
2416.	1595.2	1597.1	1599.0	1600.9	1602.8	1604.7	1606.6	1608.5	1610.4	1612.3	1.90
2415.	1576.3	1578.2	1580.1	1582.0	1583.9	1585.7	1587.6	1589.5	1591.4	1593.3	1.89
2414.	1557.5	1559.4	1561.3	1563.1	1565.0	1566.9	1568.8	1570.7	1572.5	1574.4	1.88
2413.	1538.9	1540.8	1542.6	1544.5	1546.3	1548.2	1550.1	1551.9	1553.8	1555.6	1.86
2412.	1520.3	1522.2	1524.0	1525.9	1527.7	1529.6	1531.5	1533.3	1535.2	1537.0	1.86
2411.	1501.9	1503.7	1505.6	1507.4	1509.3	1511.1	1512.9	1514.8	1516.6	1518.5	1.84
2410.	1483.6	1485.4	1487.3	1489.1	1490.9	1492.7	1494.6	1496.4	1498.2	1500.1	1.83

ELEVATION IN FEET	.0	.1	.2	.3	.4	.5	.6	.7	.8	.9	AVERAGE DIFFERENCE PER TENTH FT
2409.	1465.5	1467.3	1469.1	1470.9	1472.7	1474.5	1476.4	1478.2	1480.0	1481.8	1.81
2408.	1447.6	1449.4	1451.2	1453.0	1454.8	1456.5	1458.3	1460.1	1461.9	1463.7	1.79
2407.	1429.7	1431.5	1433.3	1435.1	1436.9	1438.6	1440.4	1442.2	1444.0	1445.8	1.79
2406.	1412.1	1413.9	1415.6	1417.4	1419.1	1420.9	1422.7	1424.4	1426.2	1427.9	1.76
2405.	1394.6	1396.3	1398.1	1399.8	1401.6	1403.3	1405.1	1406.8	1408.6	1410.3	1.75
2404.	1377.4	1379.1	1380.8	1382.6	1384.3	1386.0	1387.7	1389.4	1391.2	1392.9	1.72
2403.	1360.3	1362.0	1363.7	1365.4	1367.1	1368.8	1370.6	1372.3	1374.0	1375.7	1.71
2402.	1343.3	1345.0	1346.7	1348.4	1350.1	1351.8	1353.5	1355.2	1356.9	1358.6	1.70
2401.	1326.6	1328.3	1329.9	1331.6	1333.3	1334.9	1336.6	1338.3	1340.0	1341.6	1.67
2400.	1310.0	1311.7	1313.3	1315.0	1316.6	1318.3	1320.0	1321.6	1323.3	1324.9	1.66
2399.	1293.6	1295.2	1296.9	1298.5	1300.2	1301.8	1303.4	1305.1	1306.7	1308.4	1.64
2398.	1277.3	1278.9	1280.6	1282.2	1283.8	1285.4	1287.1	1288.7	1290.3	1292.0	1.63
2397.	1261.2	1262.8	1264.4	1266.0	1267.6	1269.2	1270.9	1272.5	1274.1	1275.7	1.61
2396.	1245.2	1246.8	1248.4	1250.0	1251.6	1253.2	1254.8	1256.4	1258.0	1259.6	1.60
2395.	1229.4	1231.0	1232.6	1234.1	1235.7	1237.3	1238.9	1240.5	1242.0	1243.6	1.58
2394.	1213.7	1215.3	1216.8	1218.4	1220.0	1221.5	1223.1	1224.7	1226.3	1227.8	1.57
2393.	1198.1	1199.7	1201.2	1202.8	1204.3	1205.9	1207.5	1209.0	1210.6	1212.1	1.56
2392.	1182.8	1184.3	1185.9	1187.4	1188.9	1190.4	1192.0	1193.5	1195.0	1196.6	1.53
2391.	1167.5	1169.0	1170.6	1172.1	1173.6	1175.1	1176.7	1178.2	1179.7	1181.3	1.53
2390.	1152.4	1153.9	1155.4	1156.9	1158.4	1159.9	1161.5	1163.0	1164.5	1166.0	1.51
2389.	1137.4	1138.9	1140.4	1141.9	1143.4	1144.9	1146.4	1147.9	1149.4	1150.9	1.50
2388.	1122.5	1124.0	1125.5	1127.0	1128.5	1129.9	1131.4	1132.9	1134.4	1135.9	1.49
2387.	1107.7	1109.2	1110.7	1112.1	1113.6	1115.1	1116.6	1118.1	1119.5	1121.0	1.48
2386.	1093.0	1094.5	1095.9	1097.4	1098.9	1100.3	1101.8	1103.3	1104.8	1106.2	1.47
2385.	1078.4	1079.9	1081.3	1082.8	1084.2	1085.7	1087.2	1088.6	1090.1	1091.5	1.46

ELEVATION IN FEET	.0	.1	.2	.3	.4	.5	.6	.7	.8	.9	AVERAGE DIFFERENCE PER TENTH FT
2384.	1063.8	1065.3	1066.7	1068.2	1069.6	1071.1	1072.6	1074.0	1075.5	1076.9	1.46
2383.	1049.3	1050.7	1052.2	1053.6	1055.1	1056.5	1058.0	1059.4	1060.9	1062.3	1.45
2382.	1034.9	1036.3	1037.8	1039.2	1040.7	1042.1	1043.5	1045.0	1046.4	1047.9	1.44
2381.	1020.6	1022.0	1023.5	1024.9	1026.3	1027.7	1029.2	1030.6	1032.0	1033.5	1.43
2380.	1006.3	1007.7	1009.2	1010.6	1012.0	1013.4	1014.9	1016.3	1017.7	1019.2	1.43
2379.	992.2	993.6	995.0	996.4	997.8	999.2	1000.7	1002.1	1003.5	1004.9	1.41
2378.	978.1	979.5	980.9	982.3	983.7	985.1	986.6	988.0	989.4	990.8	1.41
2377.	964.1	965.5	966.9	968.3	969.7	971.1	972.5	973.9	975.3	976.7	1.40
2376.	950.2	951.6	953.0	954.4	955.8	957.1	958.5	959.9	961.3	962.7	1.39
2375.	936.3	937.7	939.1	940.5	941.9	943.2	944.6	946.0	947.4	948.8	1.39
2374.	922.5	923.9	925.3	926.6	928.0	929.4	930.8	932.2	933.5	934.9	1.38
2373.	908.8	910.2	911.5	912.9	914.3	915.6	917.0	918.4	919.8	921.1	1.37
2372.	895.2	896.6	897.9	899.3	900.6	902.0	903.4	904.7	906.1	907.4	1.36
2371.	881.6	883.0	884.3	885.7	887.0	888.4	889.8	891.1	892.5	893.8	1.36
2370.	868.1	869.4	870.8	872.1	873.5	874.8	876.2	877.5	878.9	880.2	1.35
2369.	854.7	856.0	857.4	858.7	860.1	861.4	862.7	864.1	865.4	866.8	1.34
2368.	841.3	842.6	844.0	845.3	846.7	848.0	849.3	850.7	852.0	853.4	1.34
2367.	828.1	829.4	830.7	832.1	833.4	834.7	836.0	837.3	838.7	840.0	1.32
2366.	815.0	816.3	817.6	818.9	820.2	821.5	822.9	824.2	825.5	826.8	1.31
2365.	301.9	803.2	804.5	805.8	807.1	808.4	809.8	811.1	812.4	813.7	1.31
2364.	788.9	790.2	791.5	792.8	794.1	795.4	796.7	798.0	799.3	800.6	1.30
2363.	776.0	777.3	778.6	779.9	781.2	782.4	783.7	785.0	786.3	787.6	1.29
2362.	763.2	764.5	765.8	767.0	768.3	769.6	770.9	772.2	773.4	774.7	1.28
2361.	750.5	751.8	753.0	754.3	755.6	756.8	758.1	759.4	760.7	761.9	1.27
2360.	737.9	739.2	740.4	741.7	742.9	744.2	745.5	746.7	748.0	749.2	1.26

ELEVATION IN FEET	.0	.1	.2	.3	.4	.5	.6	.7	.8	.9	AVERAGE DIFFERENCE PER TENTH FT
2359.	725.3	726.6	727.8	729.1	730.3	731.6	732.9	734.1	735.4	736.6	1.26
2358.	712.8	714.0	715.3	716.5	717.8	719.0	720.3	721.5	722.8	724.0	1.25
2357.	700.4	701.6	702.9	704.1	705.4	706.6	707.8	709.1	710.3	711.6	1.24
2356.	688.0	689.2	690.5	691.7	693.0	694.2	695.4	696.7	697.9	699.2	1.24
2355.	675.7	676.9	678.2	679.4	680.6	681.8	683.1	684.3	685.5	686.8	1.23
2354.	663.5	664.7	665.9	667.2	668.4	669.6	670.8	672.0	673.3	674.5	1.22
2353.	651.4	652.6	653.8	655.0	656.2	657.4	658.7	659.9	661.1	662.3	1.21
2352.	639.3	640.5	641.7	642.9	644.1	645.3	646.6	647.8	649.0	650.2	1.21
2351.	627.3	628.5	629.7	630.9	632.1	633.3	634.5	635.7	636.9	638.1	1.20
2350.	615.3	616.5	617.7	618.9	620.1	621.3	622.5	623.7	624.9	626.1	1.20
2349.	603.4	604.6	605.8	607.0	608.2	609.3	610.5	611.7	612.9	614.1	1.19
2348.	591.6	592.8	594.0	595.1	596.3	597.5	598.7	599.9	601.0	602.2	1.18
2347.	579.8	581.0	582.2	583.3	584.5	585.7	586.9	588.1	589.2	590.4	1.18
2346.	568.1	569.3	570.4	571.6	572.8	573.9	575.1	576.3	577.5	578.6	1.17
2345.	556.5	557.7	558.8	560.0	561.1	562.3	563.5	564.6	565.8	566.9	1.16
2344.	544.9	546.1	547.2	548.4	549.5	550.7	551.9	553.0	554.2	555.3	1.16
2343.	533.4	534.5	535.7	536.8	538.0	539.1	540.3	541.4	542.6	543.7	1.15
2342.	521.9	523.0	524.2	525.3	526.5	527.6	528.8	529.9	531.1	532.2	1.15
2341.	510.5	511.6	512.8	513.9	515.1	516.2	517.3	518.5	519.6	520.8	1.14
2340.	499.2	500.3	501.5	502.6	503.7	504.8	506.0	507.1	508.2	509.4	1.13
2339.	488.0	489.1	490.2	491.4	492.5	493.6	494.7	495.8	497.0	498.1	1.12
2338.	476.7	477.8	479.0	480.1	481.2	482.3	483.5	484.6	485.7	486.9	1.13
2337.	465.6	466.7	467.8	468.9	470.0	471.1	472.3	473.4	474.5	475.6	1.11
2336.	454.5	455.6	456.7	457.8	458.9	460.0	461.2	462.3	463.4	464.5	1.11
2335.	443.5	444.6	445.7	446.8	447.9	449.0	450.1	451.2	452.3	453.4	1.10

ELEVATION IN FEET	.0	.1	.2	.3	.4	.5	.6	.7	.8	.9	AVERAGE DIFFERENCE PER TENTH FT
2334.	432.6	433.7	434.8	435.9	437.0	438.0	439.1	440.2	441.3	442.4	1.09
2333.	421.7	422.8	423.9	425.0	426.1	427.1	428.2	429.3	430.4	431.5	1.09
2332.	410.8	411.9	413.0	414.1	415.2	416.2	417.3	418.4	419.5	420.6	1.09
2331.	400.1	401.2	402.2	403.3	404.4	405.4	406.5	407.6	408.7	409.7	1.07
2330.	389.3	390.4	391.5	392.5	393.6	394.7	395.8	396.9	397.9	399.0	1.08
2329.	378.7	379.8	380.8	381.9	382.9	384.0	385.1	386.1	387.2	388.2	1.06
2328.	368.2	369.2	370.3	371.3	372.4	373.4	374.5	375.5	376.6	377.6	1.05
2327.	357.8	358.8	359.9	360.9	362.0	363.0	364.0	365.1	366.1	367.2	1.04
2326.	347.4	348.4	349.5	350.5	351.6	352.6	353.6	354.7	355.7	356.8	1.04
2325.	337.1	338.1	339.2	340.2	341.2	342.2	343.3	344.3	345.3	346.4	1.03
2324.	327.0	328.0	329.0	330.0	331.0	332.0	333.1	334.1	335.1	336.1	1.01
2323.	316.9	317.9	318.9	319.9	320.9	321.9	323.0	324.0	325.0	326.0	1.01
2322.	306.9	307.9	308.9	309.9	310.9	311.9	312.9	313.9	314.9	315.9	1.00
2321.	297.0	298.0	299.0	300.0	301.0	301.9	302.9	303.9	304.9	305.9	0.99
2320.	287.2	288.2	289.2	290.1	291.1	292.1	293.1	294.1	295.0	296.0	0.98
2319.	277.5	278.5	279.4	280.4	281.4	282.3	283.3	284.3	285.3	286.2	0.97
2318.	267.8	268.8	269.7	270.7	271.7	272.6	273.6	274.6	275.6	276.5	0.97
2317.	258.2	259.2	260.1	261.1	262.0	263.0	264.0	264.9	265.9	266.8	0.96
2316.	248.7	249.6	250.6	251.5	252.5	253.4	254.4	255.3	256.3	257.2	0.95
2315.	239.1	240.1	241.0	242.0	242.9	243.9	244.9	245.8	246.8	247.7	0.96
2314.	229.7	230.6	231.6	232.5	233.5	234.4	235.3	236.3	237.2	238.2	0.94
2313.	220.3	221.2	222.2	223.1	224.1	225.0	225.9	226.9	227.8	228.8	0.94
2312.	210.9	211.8	212.8	213.7	214.7	215.6	216.5	217.5	218.4	219.4	0.94
2311.	201.6	202.5	203.5	204.4	205.3	206.2	207.2	208.1	209.0	210.0	0.93
2310.	192.3	193.2	194.2	195.1	196.0	196.9	197.9	198.8	199.7	200.7	0.93

ELEVATION IN FEET	.0	1	.2	.3	.4	.5	.6	.7	.8	.9	AVERAGE DIFFERENCE PER TENTH FT
2309.	183.1	184.0	184.9	185.9	186.8	187.7	188.6	189.5	190.5	191.4	0.92
2308.	174.0	174.9	175.8	176.7	177.6	178.5	179.5	180.4	181.3	182.2	0.91
2307.	164.9	165.8	166.7	167.6	168.5	169.4	170.4	171.3	172.2	173.1	0.91
2306.	155.9	156.8	157.7	158.6	159.5	160.4	161.3	162.2	163.1	164.0	0.90
2305.	146.9	147.8	148.7	149.6	150.5	151.4	152.3	153.2	154.1	155.0	0.90
2304.	138.1	139.0	139.9	140.7	141.6	142.5	143.4	144.3	145.1	146.0	0.88
2303.	129.3	130.2	131.1	131.9	132.8	133.7	134.6	135.5	136.3	137.2	0.88
2302.	120.5	121.4	122.3	123.1	124.0	124.9	125.8	126.7	127.5	128.4	0.88
2301.	111.8	112.7	113.5	114.4	115.3	116.1	117.0	117.9	118.8	119.6	0.87
2300.	103.2	104.1	104.9	105.8	106.6	107.5	108.4	109.2	110.1	110.9	0.86
2299.	99.2	99.6	100.0	100.4	100.8	101.2	101.6	102.0	102.4	102.8	0.40
2298.	86.2	87.5	88.8	90.1	91.4	92.7	94.0	95.3	96.6	97.9	1.30
2297.	81.6	82.1	82.5	83.0	83.4	83.9	84.4	84.8	85.3	85.7	0.46
2296.	69.7	70.9	72.1	73.3	74.5	75.6	76.8	78.0	79.2	80.4	1.19
2295.	61.5	62.3	63.1	64.0	64.8	65.6	66.4	67.2	68.1	68.9	0.82
2294.	53.5	54.3	55.1	55.9	56.7	57.5	58.3	59.1	59.9	60.7	0.80
2293.	45.6	46.4	47.2	48.0	48.8	49.5	50.3	51.1	51.9	52.7	0.79
2292.	39.2	39.8	40.5	41.1	41.8	42.4	43.0	43.7	44.3	45.0	0.64
2291.	30.0	30.9	31.8	32.8	33.7	34.6	35.5	36.4	37.4	38.3	0.92
2290.	22.4	23.2	23.9	24.7	25.4	26.2	27.0	27.7	28.5	29.2	0.76
2289.	14.8	15.6	16.3	17.1	17.8	18.6	19.4	20.1	20.9	21.6	0.76
2288.	7.4	8.1	8.9	9.6	10.4	11.1	11.8	12.6	13.3	14.1	0.74
2287.	0.0	0.7	1.5	2.2	3.0	3.7	4.4	5.2	5.9	6.7	0.74